



MB DT ELECTRONICS

STATUS & PERSPECTIVES


CMS week

Cristina Fernández.

CERN. June 20th, 2006.

DT RO/TR ELECTRONICS

2



RESPONSIBILITIES


CIEMAT, MADRID
HEPHY, VIENNA
INFN, PADOVA
INFN, BOLOGNA
INFN, TORINO
U. AUTONOMA, MADRID

& LV, HV PS SYSTEMS

SC STATUS


CMS week.
CERN. June 20th, 2006.

SECTOR COLLECTOR (UXC55)




SECTOR COLLECTOR - MTCC STATUS

5



- 2 Crates w/BP
- 2 TIM
- 3 ROS-25
- 3 TRG SC
- 2 RO PP



SC crate: 3 units

- 2 units at CERN for Magnet Test.
- 1 at Legnaro for local integration tests.



ROS-25: 5 units

- 3 ROS-25 at CERN for Magnet Test.
- 4th ROS-25 is staying at Madrid for further testing.
- 5th ROS-25 at Torino for DDU testing.



TIM: 3 units

- 2 boards assembled and tested. They are at CERN for Magnet Test.
- 3rd at Madrid for further testing.

Ciemat Production Plans (1)

7

SC crates: 10 units

- All mechanics parts have arrived to CIEMAT.
- Mechanization of some pieces is needed.
- Assembly will start in two weeks and all crates can be ready for delivery in 4 months. Some units could be delivered sooner if needed.

TIM: 10 units + 2 spares

- Its functionality has been validated at CIEMAT and at Legnaro.
- It is a small production, PCBs are already available and are being assembled.
- They will be ready by end of the summer.
- One TIM module will be sent to Bologna in the following weeks for their tests.

Ciemat Production Plans (2)

ROS-25: 60 units + spares = 70 units

**70 ROS-25 mother boards
70 ROSCTRL mezzanines
70 GOLROS mezzanines
280 CEROS mezzanines**


- **Functionality tests have been successfully performed on the prototypes:**

**Validation tests at lab at CIEMAT,
Read-out chain with 2 DT chambers at Legnaro in local mode,
Optical link between ROS-25 and DDU,
SC to ROS-25 interface, etc.**

- **Also, during Magnet Test its functionality will be validated.**
- **Final production can start as soon as they are performed.**
- **Production will take around 6-8 months starting after validation tests.**

Trigger Sector Collector status

INFN Bologna team: F. Odorici, L. Guiducci, G. Torromeo, G. Pellegrini, R. Travaglini



Trigger Sector Collector status

10

INFN Bologna team: F. Odorici, L. Guiducci, G. Torromeo, G. Pellegrini, R. Travaglini

FULL SYSTEM TEST in preparation for MTCC


1 trigger SC board with LVDS RXs and OPTO transmission was operated in a full system test in YB+1 with cosmics.

- **connection to chamber Minicrates and chamber synchronization**
- **interface with the TTC system via TIM, and ROS25**
- **optical link to DTTF (links for 3 sectors tested)**

Trigger Sector Collector status

11

INFN Bologna team: F. Odorici, L. Guiducci, G. Torromeo, G. Pellegrini, R. Travaglini



Courtesy of Janos Ero

The three upper tracks are the Muons detected in the DT Station #1, #2 and #3, processed in the chamber minicrates, transmitted (LVDS 480 MHz at the SectColl), Opto transmitted (1.6 GHz) to the DTF and observed at the Input of the PHTF Board.

The fourth Track is the BS Trigger output for CMS.

Trigger SC Production Plans

12

INFN Bologna team: F. Odorici, L. Guiducci, G. Torromeo, G. Pellegrini, R. Travaglini

Boards	Q.ty (+ spares)	Prod start	Prod (+test) End
Opto Tx piggy	60 (15)	Jul Q1 – 2006	Dec Q4 – 2006
Opto Rx board	96 (24)	Jul Q1 – 2006	Dec Q4 – 2006
LVDS Rx 2 ch piggy	200 (40)	Jul Q1 – 2006	Dec Q4 – 2006
Mother board	60 (15)	Sep Q1 – 2006	Dec Q4 – 2006
LVDS Rx 4 ch piggy	10 (8)	Sep Q1 – 2006	Dec Q4 - 2006

LV STATUS

CMS week.
CERN. June 20th, 2006.

LV PS - MTCC Status


14

- For MTCC we have all what is needed, except:
 - Two A3050 now at Pool for acceptance tests
 - No spares except for A3009.

- Now YB+1 is working. If Pool tests are successful we can operate 2 wheels once YB+2 will be closed to YB+1.

- In case Pool tests fail we could operate MC's on YB+2 with standard PS (not under magnetic field).

LV Power Supplies



MODULES	NEEDED	SPARES	TOTAL	ORDERED	TO BE ORDERED
A3050	130	6	136	7	129
A3009	70	3	73	4	69
A3100	10	2	12	2	10
A1676A	11	1	12	2	10
A3486S	41	2	43	2	41
EASY3000S	60		60	3	57

USC55

CMS week.
CERN. June 20th, 2006.

Rack Layout in USC55 (v7.3) Lower Floor



+Z	Lower Floor (Zone S1)								
	A	B	C	D	E	F	G	H	
00	--	--	Presh. ULR	Presh. ULR	TK. FEC	TK. FEC	DT/RO/SC	--	Turbine 4U S1G00n
01	--	--	DAQ	DT TrkFnd	Opt.Cpl	RPC Trig	Pixel FEC	--	blank panel S1G00m
02	TK. Ctrl	DAQ	DAQ	DT TrkFnd	TTC	RPC Trig	Pixel Ctrl	RPC B HV	blank panel S1G00l
03	TK. Ctrl	TK. FED TIB+TID	TK. FED TOB	DT TrkFnd	%TTC	RPC Trig	Pixel FED	RPC B HV	PCI expander 1 S1G00k
04	TK. Ctrl	TK. FED TIB+TID	TK. FED TOB	CSC TrkFnd	Global	RPC Trig	Pixel FED	RPC B HV	Fan tray 2U
05	TK. Ctrl	TK. FED TIB+TID	TK. FED TOB	CSC TrkFnd	%Cal Global	%RPC Trig	DAQ	RPC B HV	PCI expander 2 S1G00i
06	TK. Ctrl	DAQ	DAQ	FBI PC	TTS	DAQ	CSC FED	RPC B HV	Heat exchanger
07	TK. Ctrl	DAQ	DAQ	DT HV	TTS	x	CSC FED	RPC B HV	DT CONTROL 1 S1G00g
*08	TK. Ctrl	TK. FED TEC-	TK. FED TEC+#	DT HV	BPTX	x#	CSC FED	RPC E+ HV	
*09	TK. Ctrl	TK. FED TEC-	TK. FED TEC+#	DT HV	LHC	DAQ#	DAQ PP	RPC E+ HV	
10	CSC HV	TK. FED TEC-	TK. FED TEC+	DT HV	BPM	DSS	ME1/1 HV	RPC E- HV	
11	CSC HV	DAQ	DAQ	DT HV	DSS	DSS	DSS	RPC E- HV	DT CONTROL 2 S1G00f
12	CSC HV	TK. Ctrl	Work Area	Work Area	Work Area	Work Area	Work Area	Work Area	Heat exchanger
13	CSC HV	TK. Ctrl	Work Area	Work Area	Work Area	Work Area	Work Area	Work Area	Blank panel S1G00d
14	CSC HV	TK. Ctrl	Work Area	Work Area	Work Area	Work Area	Work Area	Work Area	
15	Rack Pwr	TK. Ctrl	Work Area	Work Area	Work Area	Work Area	Work Area	Work Area	DDU CRATE S1G00c

<-- Passageway -->

DDU+Control (S1G00)

DT Muon Sorter: 12 Wedge Sorters + 1 Barrel Sorter

INFN Bologna: A. Montanari



• 36 Gbit/s throughput
• 8 separate clocks with PLLs

**WS: all board(12)+spares(6)
produced and tested**

- selection of 2 best muon candidates along a wedge
- ghost suppression

WS+BS successfully integrated with PHTF for MTCC: trigger generation OK!

**BS: all boards(1) + spares(2)
produced and tested**

- selection of 4 best DT muons in the barrel
- ghost suppression
- local trigger generation under programmable conditions (used in MTCC !)
- check synchronization of 12 WS
- check trigger data through spy registers

DTTF SYSTEM STATUS

19

- **PHTF: 80 boards assembled, tested (72 needed)**
- **ETTF: 15 boards assembled, tested (12 needed)**
- **WS: all boards assembled, tested (12 needed)**
- **BS: 3 boards assembled, tested (1 needed)**
- **DCC: 1 board assembled, 2nd in assembly**
- **DLI: 1 board assembled, tested, another in ass. (6 needed)**
- **TIM: 3 boards assembled, tested (7 needed)**
- **Crates: 6 DTTF crates available, 2 ass., 1 in ass.**
 - 1 Central crate – not yet arrived**
 - 1 Test crate – not yet arrived**
- **Crate controllers, control PC's: not yet arrived**

All hardware expected to be ready by September.

Time for installation: 2-3 weeks.

DT DDU/FED STATUS

20

INFN Torino: G. Dellacasa, V. Monaco

- **One pre-production board tested**
 - in Torino (LAB tests, S-link output to the Fedkit, etc.)
 - at CERN (S-link output to FRL)
 - in Legnaro (optical inputs from 2 ROS).

- **DAQ integration (local VME acquisition) performed in Legnaro.**
- **Further tests (output to FRL, TTS interface with the FMM) and final DAQ integration for the MTCC start this week at CERN.**

- **Another board is in Torino for final debugging.**
- **Still working on the debug of the TTCrx part (we are now 100% sure it's a mounting problem, electrical tests show no problems on the PCB).**

- **The TTCrx mounting problem should be fixed soon.**

Final production (5 boards+spares) planned for September.

BACKUP

CMS week.
CERN. June 20th, 2006.

ROS Production Plans



In order to speed up ROS production, an accelerated scenario is being taken into consideration:

- Mid July: Validate ROS functionality with specific tests during 1 week at CERN. (We don't need Magnet ON but full electronics chain and DAQ working).
- End July: Launch PCB production right after that to have PCBs ready by September.
- Sept-Oct: Assembly at the industry and testing at CIEMAT.
- First boards can be ready for delivery by November 06.


This plan is very optimistic and may work provided we do not find unexpected problems.

YB+2 Sector 10 and 11

Ch/MC





Sector Collector Rack YB+2




YB+1 Sector 10

Ch/MC



Sector Collector Rack YB+1



2 ROB's at the ends of the MB4(10)'s will not be read.

HV STATUS

CMS week.
CERN. June 20th, 2006.


HV POWER SUPPLIES

25

	Needed	Ordered	To be Ordered	Location
SY1527	8	8		USC55
A876	60+5(sp)	50	15	USC55
A877-12ch	180+10 (sp)	190	0	UXC55
A877-8ch	60		60	UXC55

- **Delivered modules are going to be tested at ISR.**
- **Cables (detector -> UXC) are ready and waiting for installation.**
- **Cables (UXC->USC) are bought and stored at CERN, its connectors have not yet been ordered.**
- **Patch pannels prototypes will be probably ready for cosmic challenge.**
- **Junction boxes are in process of upgrading.**

USC55: HV RACKS STATUS



LV RACK AT UXC55 (X2J21)


DRAFT

DRAFT

U	Lowest LV RACK - X2J21				P	Q	R
					input	load	Dis.
					(W)	(W)	(W)
2	DT Slow Ctrl fibres PP						
4	RPC LV crate						
6	DT LV crate						
8	DT LV crate						
10	DT LV crate						
12	DT LV crate						
14	DT LV crate						
16	DT LV crate						
18	DT LV crate						
20	DT LV crate						
22	DT LV crate						
24	DT LV crate						
26	DT LV crate						
28	DT LV crate						
30	DT LV crate						
32	DT LV crate						
34	DT LV crate						
36	DT LV crate						
38	DT LV crate						
40	DT LV crate						
42	DT LV crate						
44	DT LV crate						
46	DT LV crate						
48	DT LV crate						
50	DT LV crate						
52	DT LV crate						
54	DT LV crate						
56	DT LV crate						
58	DT LV crate						
60	DT LV crate						
62	DT LV crate						
64	DT LV crate						
66	DT LV crate						
68	DT LV crate						
70	DT LV crate						
72	DT LV crate						
74	DT LV crate						
76	DT LV crate						
78	DT LV crate						
80	DT LV crate						
82	DT LV crate						
84	DT LV crate						
86	DT LV crate						
88	DT LV crate						
90	DT LV crate						
92	DT LV crate						
94	DT LV crate						
96	DT LV crate						
98	DT LV crate						
100	DT LV crate						

53 U used
3 U free
6520 2450

- NOTE8 about extraction of crates and boxes from rack
- 8: It's the depth of crate. I assumed this as length that is needed in front of rack in order to extract the crate.
 - 9: Front extraction depth limited to 720mm in the lowest balcony (diving board)
 - 10: Front extraction depth can be more than 720mm
 - STD pieces (Turbine, heat exch. ...) have to be vented!



How the Power is calculated
 Pload [EASY CRATE] = (input variable)
 etc [EASY CRATE] = 0.75
 etc [AC/DC com] = 0.5
[See web page](#)
 Pinput = Pload/eta
 Pdis = Pload * (1-eta)/eta

NB The sketch doesn't show all the cables. Missing:

- CRATES control cables
- LV Alignment cables
- AC/DC power and RACK services cables
- Fibres

HV RACK AT UXC55 (X3J22)

DRAFT

DRAFT

U	RACK - X3J22 - proposal	P input [W]	P load [W]	P Diss. [W]
4	(D: 720mm@3KW or 645mm@2KW) Rack ctrl <i>The POWER SUPPLY is to be installed in the back - about at center</i>			
1	(D: 720 mm) heat exchanger (D: 420mm) Sect.			
6	RPC LinkBoard			
6	<i>The back of these 6 U are reserved for the power supply of the rack</i> <i>FRONT IS AVAILABE, i.e. for LV EASY CRATE I</i>			
6	(D: ---) Sect. DT HV A881			
4	DT HV Ppanel			The center of HV PP is at 31 U from bottom
6	(D: ---) Sect. DT HV A881			
7	1 U free			
6	6 U			
6	(D: 500 mm) MODULE 4-A3016 - - 4-A3016 - - 4-A3016 - - LV LB crate AC-DC conv. in common w/ not used - - not used -			
1	Distributor of cables on a 1U (if really needed) (D: 420mm) Sect.			
6	RPC LinkBoard			
1	(D: 720 mm) heat exchanger			
2	(D: 720 mm) Deflector			

43 U used
13 U free

0 0

SC RACK AT UXC55 (X2J22)

U	DT & RPC TRIGGER RACK - X2J22	DP	HW
2	DT TR/RO TTC extra lengths box		
4	Rack cooling and monitor		
1	Heat EXCHANGER + 10 slots of cables for TR/RO system (D: 420 mm)		
6	RPC LinkBoard	10	100
1	Alignment (only TR/RO) - Standard (D: 475mm)		
3	Alignment: Endcap + Unit	10	
1	Distribution of cables 1U, 3 needed		
1	DT TR/RO Sec Col. - dc (D: 500mm)		
9	DT TR/RO Sec. Col.		500
2	Distribution of cables 2U		
1	DT TR/RO Sec Col. - dc (D: 500mm)		
9	DT TR/RO Sec. Col.		500
2	Distribution of cables 2U		
1	DT TR/RO Sec Col. - dc (D: 420 mm)		
6	RPC LinkBoard	10	100
2	Deflector		
2	DT TR/RO TTC extra lengths box		

53 U used
3 U free

1330 [W]

NOTES about extraction of crates and boxes from rack

- * D: it's the depth of crate. I assumed this as length that is needed in front of rack in order to extract the crate.
- * Front extraction depth limited to 720mm in the lowest balcony (diving board)
- * 45 U Front extraction depth can be more than 720mm
- * STD pieces (Turbine, heat exch. ...) have to be verified!



NB The sketch doesn't show all the cables. Missing:
- DT-tr-o cables other than MB.CA.tr & MB.CA.ro
- Alignment cables
- RPC cables